

9TH MARCH, 2023

TO: ALL BIDDERS

ADDENDUM No. 1

TENDER No. KWS/ONT/B&F/44/2022-2023: HYDRO - GEOLOGICAL SURVEY, DRILLING AND EQUIPPING OF 1 NO. BOREHOLE AT KASAALA GATE - TSAVO EAST NATIONAL PARK

TENDER CLARIFICATION -

Pursuant to Section 75 of the PPADA, 2015, Kenya Wildlife Service wishes to clarify the following: -

SECTION V- BILL OF QUANTITIES

Referenc e No.	1. Preliminary and General Items
1.11	Delete Allow for profits for items 1.11 & 1.12 and replace with Allow for profits for item 1.7 & 1.8

Referenc e No.	2. Borehole Drilling, Development and Test Pumping (Provisional Depth = <u>250m</u>)
2.2	Drilling of a 355mm bore from 0 – 200m <i>The bore is the hole</i>
2.3	Delete Ditto but n.e. exceeding 200 – 200m and replace with Ditto but n.e exceeding 300m
2.3	Supply and installation of plain steel 152mm Class B steel casing – 4.5mm thickness
2.7	Anticipated pump yield: The Contractor to carry out 24 hrs test and 12 hrs recovery measurements to ascertain the borehole yield.

Note: Items related to the depth are PROVISIONAL and shall be re - measured

Reference No.	3. Pump, Solar, panels and Support structures
3.1	Submersible water pump - <i>Contractor to size</i>
3.2	Starter motor (<i>contractor to specify based on sized pump duty</i>)
3.4	6mm ² four core submersible cable – 280m (<i>to allow for connection to panel</i>)
3.6	2.5" borehole upvc pipes – Heavy duty (<i>60 pcs is provisional</i>)
3.12	Electrode cable for probes – Black: 280m (<i>to allow for connection to the panel</i>)
3.13	Electrode cable for probes – Brown: - <i>Ditto as in 3.12 above</i>
3.5	250 Watts Solar panels: 80 pcs
3.23	Float Switch – Contractor to specify

NB

1. This addendum shall be construed to form part of the tender
2. The closing date of the tender has been moved from 10th March, 2023 to **Thursday 16th March 2023** at the same time and place.
3. All other terms and conditions in the tender remain.

DEPUTY DIRECTOR – SUPPLY CHAIN MANAGEMENT
For: DIRECTOR GENERAL